





LANDSCAPE REQUIREMENTS (PER GRAND PRAIRIE U.D.C. & CORRIDOR OVERLAY DISTRICT STANDARDS) PD-297C		
SITE AREA (8.08 ACRES) = 350.992 S.F.		
000,002 0.1	REQUIRED	PROVIDED
MIN. 15% LANDSCAPE AREA FOR SITE 350,992 S.F. X 15% = 52,648 S.F.	52,648 S.F.	68,340 S.F. OR 19%
30' LANDSCAPE BUFFER AT PUBLIC STREET ADJOINING ALL PARKING AREAS		
690'-6" ROBINSON ROAD (30 X 691) = 20,730 SF 552'-2" FORUM DRIVE (30 X 553) = 16,590 SF	(30 X 691) = 20,730 SF (30 X 553) = 16,590 SF	20,730 S.F. 10,987 S.F.
1 TREE PER 500 S.F. OF REQ. LANDSCAPE AREA 52,468 S.F. / 500 = 105.296 TREES	106 TREES	106 (3" CAL.) TREES
1 SHRUB PER 50 S.F. OF REQ. LANDSCAPE AREA 52,468 S.F. / 50 = 1,052.96 SHRUBS	1,053 SHRUBS	1,060 SHRUBS
1 TREE PER 20 PARKING SPACES 329 PARKING SPACES / 20 = 16.45 TREES	17 TREES	17 TREES (PT)
NO PARKING SPACE SHALL BE LOCATED GREATER THAN 100' FROM THE CENTER OF A TREE		YES
PARKING AREAS SHALL BE SCREENED ALONG ALL STREETS BY A MIN. 3' HT. SOLID SHRUB HEDGE, BERM, FENCE, OR COMBINATION OF THESE.		YES








SET SHRUBS VERTICAL. SHRUB SPACING AS PER PLANS. LAYOUT VARIES, PRISHED GRACE OF SHRUB BED TO BE 2" BELDW ADJACENT FINISH GRADE AT EDGE TO HOLD MULCH. PLANT TOP OF ROOTBALL AT GRACE.











BE ESSEW FOR TE COLD TORY BAPPROVATRUCTION BGO erchitects 4202 Beltway Drive Addison, TX 75001 214.520.8878 bgoarchitects.com

CARLETON RESIDENTIAL PROPERTIES

REVISIONS

PHASE

DRIVE

FORUM

02-20-18

17222

SHEET NUMBER LP0.02

LANDSCAPE PLAN